



**5173 Campbells Run Road
Pittsburgh, PA 15205**

P: 412-494-0510

F: 412-494-0426

BID DATE & TIME: *May 5, 2017 - 10:15 AM*

OWNER: City of Clairton

CONTRACT NO.: 2017-02

PROJECT NAME: 2017 Milling and Resurfacing

ENGINEER'S ESTIMATE: \$600,000

PROJECT DESCRIPTION: The work under Contract No. 2017-02 generally consists of pavement maintenance on various roads throughout the City. Work includes, but is not limited to, the milling of existing bituminous and concrete pavements, resurfacing and overlay, all excavation, grade adjustments, and final restoration. Base repair is included in the Contract as an allowance only to be used when required for proper installation of binder and wearing courses.

All bituminous milling in this Contract is to be to an average depth of 2.5 or 4.0 inches. All concrete milling is to be an average depth of 2.5 inches. All 9.5mm HMA leveling is to be a depth of 1.0 inches. All wearing course placement is to be a depth of 1.5 inches.

PLANS & SPECIFICATIONS: \$110.00 -- *Non-Refundable*

PROJECT ENGINEERS: Robinson