



**5173 Campbells Run Road  
Pittsburgh, PA 15205**

**P: 412-494-0510**

**F: 412-494-0426**

**BID DATE & TIME:** *August 11, 2017 @ 10:00 AM*

**OWNER:** Creswell Heights Joint Authority

**CONTRACT NO.:** 2017-03A, B, C

**PROJECT NAME:** 2017-03A: North Street 36" Water Main Installation  
Water Treatment Plant Improvements

2017-03AB, 03C: Route 51 Water Main Installation

**PROJECT DESCRIPTION:**

The work under Contract No. 2017-03A generally consists of the construction of approximately 175 lineal feet of 36" ductile iron water main and appurtenances reduced to 16 inch for extension across Route 51 by Contract 2017-03B. All waterline construction is installed via open cut construction methods and is located within the paving limits of North Street and requires all restoration of disturbed areas. Work under Contract 2017-03A includes demolition of an existing buried Chlorine Contact Tank. Included in this Contract is extension of ¾ inch chemical testing lines and their connection inside the Water Treatment Plant Building.

The work under Contract No. 2017-02B and Contract 2017-03C generally consists of the construction of approximately 223 lineal feet of 16 inch and 8 inch ductile iron water main and appurtenances. Contract 2017-03B Construction commences at the north side of Route 51 where the 16 inch Ductile Iron Pipe extends across Route 51 inside a 24 inch steel pipe casing. On the south side of Route 51 the 16 inch pipe line is reduced to eight inch Ductile Iron Waterline and connects to an existing 8 inch water main. Contract 2017-03C is construction replacing an 8 inch Trainsite Pipe waterline extending approximately 200 feet south along

Route 51. All new waterlines are installed via open cut construction methods and are located within the paving limits of PA State Highway Route 51 and requires restoration of all disturbed areas.

**PLANS & SPECIFICATIONS:** \$65.00 -- *Non-Refundable*

**PROJECT ENGINEERS:** Soster / R. Hoffman / Coldren