



**5173 Campbells Run Road  
Pittsburgh, PA 15205**

**P: 412-494-0510**

**F: 412-494-0426**

**BID DATE & TIME:** *February 9, 2018 – 10:00 AM*

**OWNER:** Creswell Heights Joint Authority

**CONTRACT NO.:** 2018-01

**PROJECT NAME:** North Street 36" Water Main Installation / WTP Improvements

**ENGINEER'S ESTIMATE** \$600,000.00

**PROJECT DESCRIPTION:** The work under Contract No. 2018-01 generally consists of the construction of approximately 240 lineal feet of 36" ductile iron water main and appurtenances reduced to 16 inch for extension across Route 51. Construction commences at the CHJA Water Treatment Plant and continues through the north side of Route 51 intersection with North Street where the 36 inch line is reduced to 16 inch waterline and extends across Route 51 inside a 24 inch steel pipe casing. On the south side of Route 51 the 16 inch pipe line is reduced to 8 inch Ductile Iron Waterline and connects to an existing 8 inch water main. All waterline construction is installed via open cut construction methods and is located within the paving limits of North Street and requires all restoration of disturbed areas. Work under Contract 2018-01 includes demolition of an existing buried Chlorine Contact Tank. Included in this Contract is extension of ¾ inch chemical testing lines and their connection inside the Water Treatment Plant Building.

**PLANS & SPECIFICATIONS:** \$65.00 -- *Non-Refundable*

**PROJECT ENGINEERS:** Pasko / Soster