



**5173 Campbells Run Road
Pittsburgh, PA 15205**

P: 412-494-0510

F: 412-494-0426

BID DATE & TIME: *January 22, 2018 – 1:00 PM*

MANDATORY PRE-BID MEETING: **January 10, 2018 – 10:00 AM**
Authority Office

OWNER: Authority of the Borough of Charleroi

CONTRACT NO.: 2017-04A, B
2017-05

PROJECT NAME: 2017-04A,B - S.R. 0088 Utility Relocation
2017-05 - 16" Transmission Main WTP to 2nd

ENGINEER'S ESTIMATE: 2017-04A, B - \$530,000
2017-05 - \$480,000

PROJECT DESCRIPTION: The Work under Contract No. 2017-04A generally consists of the installation of a total of approximately 1,535 LF of 12" C900 PVC DR14, 16" C905 PVC DR18, and 12" HDPE DR9 water main, valves, fittings, appurtenances, etc. as shown on the Contract Drawings. The Work includes installation of two parallel 12" HDPE DR9 water mains, each approximately 135 LF in length, under Maple Creek via the directional drilling method.

The Work under Contract No. 2017-04B generally consists of the installation of approximately 125 LF of 20" HDPE DR17 DIPS force main and appurtenances using the directional drilling method.

The Work under Contract No. 2017-05 generally consists of the installation of a total of approximately 1,470 LF of 8" C900 PVC DR14 and 16" C905 PVC DR18 water main, valves, fittings, hydrants, services, appurtenances, etc. as shown on the Contract Drawings.

PLANS & SPECIFICATIONS: \$125.00 -- *Non-Refundable*

PROJECT ENGINEERS: Rosensteel/Gibson

