



**5173 Campbells Run Road
Pittsburgh, PA 15205**

**P: 412-494-0510
F: 412-494-0426**

BID DATE & TIME: *June 19, 2018 – 11:00 AM*

OWNER: Charleroi Area School District

CONTRACT NO.: 2018-01

PROJECT NAME: 2018 Entrance and Parking Paving Project

PROJECT DESCRIPTION: See below

PLANS & SPECIFICATIONS: \$85.00 -- *Non-Refundable*

PROJECT ENGINEERS: Dei Cas

The work under Contract No. 2018-01 **Base Bid**

Milling Existing Pavement 2" inches Depth.	6780/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	750/Tons
Furnish and Install 1 foot wide Geo Composite Membrane, as per Technical Specification Complete	2300/LF
Furnish, excavate, and install Road Base repair, as per Plans and Specifications, Complete	1270 /SY
Furnish and Install new concrete gutter 6" thick to match existing concrete gutter as shown on the plans	47/SY
Furnish and Install new 2' x 4' precast concrete inlets with cast iron bicycle safe grates, as shown on plans and	7/EA

specifications, complete	
Furnish and Install 12"diameter-12 smooth wall plastic storm sewer pipe, as per plans and specifications, complete	1150/LF
Furnish and install 12" diameter N-12 Fittings (90,45,tee) as necessary for storm sewer pipe, Complete	4/EA
Furnish and install 3'wide x 10'long Gabion energy dissipaters, Complete	3/EA
Tie New Storm Sewer into existing storm sewer, Complete	1/EA
Tie New Storm Sewer into existing inlet, Complete	1/EA
Furnish and install 3'wide x 1'deep #3 stone shoulder as shown on plans, Complete	215/LF
Furnish and install Used type 2S Guide Rail as shown on Plans and specifications	2040/LF
Furnish and install new type 2S Terminal Sections as per plans and specifications, Complete	4/EA
Provide Project Traffic Control, Complete Project	Lump Sum
Project Mobilization, Complete Project	Lump Sum

Alternate # 1

Milling Existing Pavement 2" inches Depth.	660/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	75/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	660/LF

Alternate # 2

Milling Existing Pavement 2" inches Depth.	5410/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	600/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	5410/LF
Furnish, excavate, and install Road Base repair, as per Plans and Specifications, Complete	23 /SY
Furnish and Install 18" plain cement concrete curb, as shown on drawings and specifications, Complete	201/LF

Alternate # 3

Milling Existing Pavement 2" inches Depth.	10523/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	1160/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	10523/LF

Alternate # 4

Milling Existing Pavement 2" inches Depth.	1250/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	140/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	1250/LF
Furnish, excavate, and install Road Base repair, as per Plans and Specifications, Complete	23 /SY

Alternate # 5

Milling Existing Pavement 2" inches Depth.	2340/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	260/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	2360/LF
Furnish and Install 18" plain cement concrete curb, as shown on drawings and specifications, Complete	360/LF
Furnish and Install new 2' x 4' precast concrete inlets with cast iron bicycle safe grates, as shown on plans and specifications, complete	5/EA
Furnish and Install 12" diameter-12 smooth wall plastic storm sewer pipe, as per plans and specifications, complete	445/LF
Furnish and install 3' wide x 10' long Gabion energy dissipaters, Complete	3/EA
Furnish and Install 4" thick plain cement concrete sidewalk as shown on drawings and specifications, Complete	14/SY

Alternate # 6

Milling Existing Pavement 2" inches Depth.	575/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	65/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	575/LF

Alternate # 7

Milling Existing Pavement 2" inches Depth.	2340/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	260/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	2340/LF
Furnish and Install 18" plain cement concrete curb, as shown on drawings and specifications, Complete	120/LF
Furnish and Install Cross Walk Paint at Service Road, Complete	1/LS

Alternate # 8

Milling Existing Pavement 2" inches Depth.	870/SY
Furnish and Install "Superpave" Wearing Course 9.5mm 2" depth after compaction, Complete	100/Tons
Furnish and Install Petro Mat Paving Fabric, as per Technical Specification Complete	870/LF